JHARKHAND STATE KHADI & VILLAGE INDUSTRIES BOARD, UDYOG BHAWAN RATU ROAD RANCHI

SHORT NOTICE INVITING TENDER

Sealed tenders are invited in prescribed manner from eligible firms/agencies for proposal/execution of following work:-

Name of Work:-

- 1. Name & Address of person inviting tender: Chief Executive Officer, JSKVIB, Ranchi
- 2. Date of sale/ Downloading the tender document from 24-11-2023.
- 3. Date and time of receipt of tender: 05-12-2023 (upto 5.00 PM.)
- 4. Date and time of opening of tender: 06-12-2023 (at 11.00 AM.)
- 5. Place of sale of Tender Document- Office of CEO, JSKVIB Udyog Bhawan Ratu Road Ranchi.
- 6. Place of receipt and opening of Tender: Office of The CEO, JSKVIB Udyog Bhawan Ratu Road Ranchi 834001.

7. **Details of Work:**

Sl. no.	NIT No	Name of work	Estimated Cost	Amount of E.M.D (Rupees)	Cost of Tender Document)	Time of Completion
01	06/JSKVIB/2023-24	Repairing, Interior and Furnishing work of Khadi Emporium at old Vidhan Sabha, Ranchi	Rs. 4,77,392.00	9550.00	750.00	1 Months
02	07/JSKVIB/2023-24	Repairing, Interior and Furnishing work of Khadi Emporium at Dudhani, Dumka	Rs. 15,86,917.00	31740.00	5000.00	1 Months
03	08 7JSKVIB/2023-24	Repairing, Interior and Furnishing work of Khadi Emporium at New Delhi	Rs. 21,45,252.00	42910.00	5000.00	1 Months

8. For further details please Visit the Website:- www.jharkhandkhadi.net

SD/-Chief Executive Officer

Se de la maria

OFFICE OF THE CHIEF EXECUTIVE OFFICER JHARKHAND STATE KHADI AND VILLAGE INDUSTRIES BOARD, UDYOG BHAWAN RATU ROAD, RANCHI

CHAPTER-I

Sealed tenders are invited in prescribed manner from eligible firms/agencies for proposal /execution of following works.

Name of work -1. Repairing, Interior and furnishing work of Khadi Emporium at New Delhi.

Eligibility Criteria : -

- (a) The intending tender must have in its name as a prime contractor experience of having successfully completed similar nature of work (three years minimum).
- (b) Similar nature of work means interior furnishing work and renovation work of emporium in govt. sector.
- 2. It is essential to annex self-attested Xerox copy of Up-to-date registration paper, up-to-date PAN card and sales tax clearance certificate, Audit report of back three years. The tenderer must have achieved an annual turnover of INR 70 Lacs in any year during the preceding 3 (Three) Financial Year along with tender Document in envelope containing technical bid.
- 3. Tender Document can be purchased on deposit of amount Rs. 5000/-in shape of Demand Draft in favour of Chief Executive Officer Jharkhand State Khadi And Village Industries Board (Non-refundable) payable at Ranchi from 24/11/2023 to 05/12/2023 on working days during office hours. Tender document may also be Downloaded on :www.jharkhandkhadi.net. But at time of time deposit of tender, tenders should deposit tender fee along with tender.
- 4.(a) Ten tender are required to deposit Earnest Money along with tender, as mentioned in Sl. No. 7 of NIT in shape of Bank Draft from my nationalized Bank in favour of Chief Executive Officer Jharkhand State Khadi and Village Industries Board.
- 5.(b) The quotation the tender should visit the site and only after visiting the actual condition of the site and getting satisfied with them, they should submit their details Estimate and quote their rate item ways in separate envelop.
- Conditional tender will not be accepted.

Rest Many

The contractor has to supply all the materials, tools & plant required in construction at their own cost and department will not make available any construction materials or Plant.

- 8. Office of undersigned may be contacted for any further information /clarification.
- For other information like drawings, special term and condition, quotation can consult the office of the undersigned.
- 10. The undersigned reserves the right to reject any or all the tenders or postpone the tender without assigning any reasons there off.

SD/-

Chief Executive Officer Jharkhand State Khadi& Village Industries Board, UdyogBhawan, Ratu Road, Ranchi

2.11.2023

Chapter -II

- 1. Sealed tender for work as per NIT group will be received from registered eligible contractors upto 5.00 PM. On 05/12/2023 by Chief Executive Officer, Registered eligible contractor can participate in this tender. The bid will be opened by the JSKVIB Ranchi on 06/12/2023 at 11.00 AM The tender or their authorized representative.
- 2. Tender shall be submitted in a big sealed envelope containing the Technical Bid and the Financial Bid.
- a. The Employee containing Technical Bid should contain the Documents in support of meeting eligibility criteria (vide clause I of chapter1 of under documents. Earnest money in acceptance
- b. The Envelope concealing Financial Bid should contain their financial rates as per submitted Detailed Estimate item wise.
- 3. The work is to be completed in all respects within the time mentioned in NIT from the date of written order to commence the work. The items of work, plan, specification or may information in connection with the work can be seen in the office of the CEO. JSKVIB Ranchi on any working day during office hours before filling tender.
- 4. Along with item of work tender document can be purchased from the office of the CEO JSKVIB on payment of the cost of tender paper as mentioned in clause 8 (details of work) of NIT only in shape of account payee Bank Draft in favour of JSKVIB Ranchi (non-refundable) on any working day during working hours from 24/11/2023 to 05/12/2023 Tender document may also be Downloaded on –www.jharkhandkhadi.net but at time of time deposit of tender, tenders should deposit tender fee along with tender No tender paper will be sold by office on the date fixed for selling the tender.
- 5. Earnest Money (E.M.D.) as mentioned in para in Clause 7 of NIT only in shape of Bank Draft from any nationalized Bank in favour of Chief Executive Officer, Jharkhand State Khadi and village industries Board Payable at Ranchi.
- 6. Tender not submitted with required Earnest Money in the prescribed shape shall be out rightly rejected and will have no place in the comparative statement.
- 7. Tenderer should submit Detail Estiamte as per given item of work, drawing & Design by the visit the side with the tender document and quote his/her their rate in time wise as per submitted detail estimate.

JE. 84 11.22 3

- Tenderer shall enclose Xerox copy of her/his/their registration in is certificate and exemption certificate, if any, in absence of which the tenders may not be considered.
- Up-to-date sales tax clearance certificate, audit report of last three years, Annual Turnover of INR 70 Lacs in any year during the proceeding 3 (three) Financial Years.
 - Authority reserves the right to reject any or all the Tenders received or to allot the work 10. to one or more contractors without assigning any reasons thereof.
- In case of successful tenderer, deposit of 5% of tender value as Initial security deposit is 11. to be deposited by successful tendere before agreement in the form of Demand Draft in favour of C.E.O. JSKVIB total security deposit will be 10% of the tendered amount and the remaining 5% shall be recovered from the contractor by deduction from his remaining account bills @5% of the total amount of each bill.
- The Earnest Money of successful tenderer which accompanies the tender will be forfeited in case of the tenderer decline to sign the agreement or contract or to deposit security 12. money within 10 days of being called upon to do so, after approval of tender by competent authority.
- The NIT with general rules and special conditions will from a part of the document. 13.

SD/-

Chief Executive Officer Jharkhand State Khadi& Village Industries Board, UdyogBhawan, Ratu Road, Ranchi

CHAPTER III

GENERAL RULES

- The complete tender with all its enclosure shall be enclosed in sealed envelope and delivered to the office of C.E.O, JSKVIB, Udyog Bhawan Ratu Road Ranchi on date and time as stipulated in NIT clause 3.
- 2. The tenderer should mention in his forwarding letter a list of all documents submitted with the tender.
- 3. The tender shall contain the full name, address of residence and place of business of person or persons filling the tender. In case there is subsequent change in address it must be informed to the office of the C.E.O, JSKVIB, Udyog Bhawan Ratu Road Ranchi by registered post with AD.
- 4. All pages of tender documents, and general rules and must be signed with stamp, at the lower left hand corner and where ever required in the tender paper by the tenderer or a person holding power of attorney authorised to sign on behalf of the partners before submission of the tender.
- 5. In the event of the tender submitted by a firm it must be signed by each partner thereof and in the event absence of any of the partner, the power of attorney authorising him to do so must be produced on demand. All signatures should be dated.
- 6. The rates quoted by the tenderer shall be inclusive of Income Tax, Sales Tax, Labour cess, Royalty or any other State and Central taxes applicable.
- 7. The tenderer shall be presumed to have carefully gone through the conditions of the contract and specifications of the work. The tenderer will also be deemed to have inspected the work site and to have satisfied herself/himself/themselves Independently as to the nature, extent and practicability of all works, required roads, approach and other means of communication and access to the site available, accommodations and buildings that may be required for temporary purposes in connection with the contract work and also availability of construction materials, locations of work site including it climate other geological characteristics, availability of skilled, semi-skilled unskilled labourers etc. The consequence of the lack of necessary knowledge will be at the risk and cost of the tenderer.
- 8. The tenderer must be submit work programme of the work in technical bid of the tender.

86:06 13.00 3

- All labours are to be paid as per minimum wages act in force and as revised from time to time during the execution of work.
- 10. The Tenderer will provide labour huts drinking water/medical facilities to labours at and keep the site clear at his own cost.
 - 11. The tenderer must return all the tnder papers duly signed with stamped on each paper while submitting the tender, failing which the same may be considered invalid.
 - 12.On receipt of written order from the Authority, JSKVIB Ranchi, the successful tender will first deposit the balance amount of initial security deposit (SD) within the specification period of ten days and then enter into an agreement with the JSKVIB Ranchi on the of stipulation in the approved tender document along with subsequent negotiation terms as mutually agreed upon before issue of work order. Written order to commence work shall be issued by the JSKVIB after acceptance of agreement by the competent authority.

SD/-

Chief Executive Officer Jharkhand State Khadi Village Industries Board, UdyogBhawan Ratu Road, Ranchi.

PE 76 12013

Bill of Quantity.

Name of work:- furnishing work of Khadi Emporium at New Delhi.

THE RATES OF ITEMS ARE BASED ON CURRENT JHARKHAND S.O.R. of B.C.D - July 2022 and DSR 2021

Sl	2022 and DSR 2021	04 11 11 7			
No.	Description	Qty	Unit	Rate	Amount
1	Dismantling ceiling work in floors and roofs laid in cement mortar including stacking material within 50 meters lead	181.65	m2		
2	Providing and fixing aluminium die cast body tubular type universal hydraulic door closer (having brand logo with ISI, IS: 3564, embossed on the body, door weight upto 35 kg and door width upto 700 mm), with necessary accessories and screws etc. Complete	5.00	Nos.		
3	Extra for cleaning the old surface by scraping the entire old white wash or colour wash-do-do-all complete job as per direction of E/I.	181.65	m2		
4	Providing and applying plaster of paris putty of 2 mm thickness over	181.65	m2		
5	Providing two coats of plastic emulsion paint of approved shade and make over a coat of cement primer over new surface including preparing plastered surface by rubbing smooth with pumice stone or fine sand paper, applying putty wherever required, scaffolding washing of floor and taxes all complete as per building specification and direction of E/I	181.65	m2		
6	Providing primer one coat of red lead paint of approved make over steel surface including preparing the surface after cleaning removing dirt, scales, grease and sand papering, including cost of scaffolding etc. all complete as per building specification direction of E/I	181.65	m2		
7	Providing and fixing in positionthick wooden floor made of 10mm thick well seasoned flooring with all necessary Hardware and fittings including ISI marked designs approved by engineer with necessary screws. 35 mm thick including ISI marked stainless steel screws. Decorative wooden floor one side decorative same as mica or commercial design on other face (Type1) conforming to IS 1328 BWR Type Make lamiwood and others .Flooring	45.83	m2		
8	Providing 2 coats of synthetic Enamel paint of approved shade and make over steel surface grills & railings including cleaning the surface thoroughly scaffolding and axes all complete as per building specification and direction of E/I.	74.93	m2		
9	Providing and fixing in wall lining flat pressed three layer (medium density) particle board or graded wood Pre-laminated one side decorative, lamination and other side balancing lamination Grade I, Type II, IS:12823 marked, including priming coat on unexposed arrangement and screws etc. complete:25 mm thick retardant.	68.60	m2		
10	Providing and fixing 12 mm thick panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick. Fire retardant plywood conforming to 1S: 5509		m2		

E. 46 /11.0003


12	Designing. providing, installing and fixing factory finished custom designed cold form Light Gauge Steel Framed super structure comprising of steel wall panel, trusses, purlins etc manufactured out of minimum 0.75 mm thick steel sheet as per design requirements. The steel sheet shall be galvanized (AZ-150gms Aluminium Zinc Alloy coated steel having minimum yield strength 300-550 Mpa) conforming to AISI specifications and IBC 2009 for cold formed steel framing and construction and also as per 18: 875-1987, ISO 800-1984 and IS:801-1975. The wind load shall be as per provisions of 18-875 (part -III), LGSFS frame shall be designed as per IS: 801 using commercially available software such as Frame CAD Pro-11.7/ STAAD PRO-V8i/ ArchitekV2.5.16/ Revit architecture-2011 or equivalent. Proper usage of Connection Accessories like Heavy Duty Tension Ties, Light Duty Hold-ons, Twist Straps (to connect truss with wall frames). Strong Tie, Tie Rod, H-Brackets, Boxing Sections, L-Shaped Angles for better structural stability. The framing section shall be cold form C-type having minimum web depth 89 mm x 39mm flange x 11mm lip in required length as per structural design requirement duly punched with dimple/ slot at required locations as per approved drawings. The slots will be along centre line of webs and shall be spaced minimum 250mm away from both ends of the member. The frame can be supplied in panelized or knock down condition in specific dimensions and fastened with screws extending through the steel beyond by minimum of three exposed threads. All self drilling tapping screws for joining the members shall have a Type II coating in accordance with ASTM B633(13) or . Providing and laying 300x300mm size ceramic floor tiles-do-do-all	580.00	KG		
13	complete job as per direction of E/I. Providing and laying 6mm thick precast white glazed tiles-do-do-all	21.74	m2		
14	complete job as per direction of E/I. Designing. fabricating, testing, installing and fixing in position Curtain Wall with Aluminium Composite Panel Cladding, with open grooves for linear as well as curvilinear portions of the building, for all heights and all levels etc. including: (a) Structural analysis & design and preparation of shop drawings for pressure equalisation or rain screen principle as required, proper drainage of water to make it watertight including checking of all the structural and functional design. Code Description Unit Rate No. 163 SUB HEAD: 8.0 CLADDING WORK (b) Providing, fabricating and supplying and fixing panels of aluminium composite panel fadding in pan shape in metalic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoropolymer resin coating of approved colour and shade on face # 1 and polymer (Service) coating on face # 2 as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc. (c) The fastening brackets of Aluminium alloy 6005 T5 / MS with Hot Dip Galvanised with serrations and serrated washers to arrest the wind load movement, fasteners, SS 316 Pins and anchor bolts of approved make in SS 316. Nylon separators to prevent bi-metallic contacts all complete required to perform as per specification and drawing The item includes required to perform as per specification and drawing The item includes cost of all material & labour component, the cost of all mock ups at site, cost of all samples of the individual components for testing in an approved laboratory, field tests on the assembled working curtain wall with aluminium composite panel.	14.74	m2		



	Providing and fixing factory made Fiberglass Reinforced plastics (F.R.P.) chajja 4 mm thick of required colour, size and design made by Resin Transfer Moulding (RTM) Machine Technology, resulting in void free compact laminate in single piece, having smooth gradual slope curvature for easy drainage of water and duly reinforced by 2 nos vertically and 1 nos horizontally 50x2 mm thick M.S. flat with 12 mm in built hole for grouting on the existing wall along with the 50 mm flanges duly inserted and sealed in the wall complete in one single piece casted monolithically, including all necessary fittings. The FRP Chajja should be manufactured using unsaturated Polyester resin as per 18: 6746, duly reinforced with fibre glass chopped strand mat (CSM) as per 18: 11551 complete with protective Gel coat U/V coating on Top for complete resistance from the extreme of temperature, weather & sunlight (Only plan area of chajjas shall be measured for making payment)	14.74	m2 \	
16	Description Providing and supplying aluminium extruded tubular and other aluminium sections as per the architectural drawings and approved shop drawings, the aluminium quality as per grade 6063 T5 or T6 as per BS 1474,including super durable powder coating of 60-80 microns conforming to AAMA 2604 of required colour and shade as approved by the Engineer-in-Charge. (The item includes cost of material such as cleats, sleeves, screws etc. necessary for fabrication of extruded aluminium frame work. Nothing extra shall be paid on this account). The weight of aluminium extruded section shall be taken for purpose of payment, 256kg	256.00	Kg	
17	Providing and fixing ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped gaivanized steel sections (galvanized@120 grams/sqm, both side inclusive) consisting of main 'T' runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main"T" runners to be suspended from celling suing GI slotted cleas of size 27x37x25x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm fixed to ceiling with galvanized butterfly level clips of size 85x30x0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-Sections shall be pre-painted with polyesterpaint, all complete for all heights as per specifications, drawings and as directed	181.64	m2	
18	by Engineer in charge.	1.00	No.	
19	Providing and fixing one piece construction white vitreous china squatting plate with an integral longitudinal flushing pipe, white P.V.C. automatic flushing cistern, with fittings, standard size G.I. / PVC flush pipe for back and front flush with standard spreader pipes with fittings, G.I clamps and C.P. brass coupling complete, including painting of fittings and cutting and making good the walls and floors etc. wherever required: 17.6.1		No.	
	is a siel both fittings-do-do-all complete Job as per direction	6.00	Nos.	
1	Supply special batti fittings as	0.0		



	Stop	Cock	3.00	Nos.	
	Shov	we Rose	1.00	No.	
	Tow	el Rail	1.00	No.	
	Soa	p dish	2.00	Nos.	
	Gla	ss shelf	4.00	Nos.	
	Mir	ror	1.00	No	
21	wit flu (ha co wl	oviding and fixing water closet squatting pan (Indian type W.C. pan) th 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. shing cistern, including flush pipe, with manually controlled device andle lever) conforming to IS: 7231, with all fittings and fixtures implete, including cutting and making good the walls and floors herever required: 17.1.1 White Vitreous china Orissa pattern W.C. pan is size 580x440 mm with integral type foot rests	1.00	Nos.	
	1	lectricak work.			
22	f (roviding and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. lushing cistern, including flush pipe, with manually controlled device handle lever) conforming to IS: 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: 17.1.1 White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	75.00	Point	
23	3	Twin control point wiring in PVC conduit with Modular type switch: Wiring for twin control light point with 1.5Sq.mm FRPVC insulated copper conductor single core cable in surface/recessed PVC conduit, 2way Modular type switch,phenolic laminated sheet sheet,suitable size PVC/G.l.box etc.as required. 9	96.00	Point	
2	24	Power plug wiring in PVC conduit(2x4Sq.mm) Wiring for light/power plug with 2x4Sq.mm FRPVC insulated copper conductor single core cable in surface or in recessed PVC conduit along with 1No4Sq.mm FRPVC insulated copper conductor single core cable for loop earthing etc. as required	460.00	Point	
	25	Circuit/submain wiring PVC conduit:- Wiring for circuit/submain withing along with earth wire with the following sizes in PVC insulated copper conductor single core cable in surface/ recessed PVC conduit as required			
		2x1.5Sqw.mm+1x1.5Sq.mm earth wire	100.00	Meter	
	26	23/2.55 a mm+1×2.55a mm earth wire	100.00	Meter	
	26	S/F piano type switch/socket:- Supplying and fixing of following modular type switch/socket on the existing switch box/cover including connection etc.as required.		Fach	
		5/6Amp one way switch 60 each	60.00	Each Each	
	28	3pin 5Amp socket outlet 41 each	41.00 25.00	Each	
	29	15/16 A see S. S. combined 25 each	25.00	Lacii	
	30	it-b/speket: Supplying and fixing of following modular		Cock	
		5 September (Deluve) 15 each	15.00	Each	
	31	S/F light plug point with piano type Accessories: Supplying and fixing suitable size modular type G.I./PVC box on surface or in recess with phenolic laminated sheet cover infront including providing and fixing 5Pin 5/6Amp socket outlet and 5/6Amp piano type switch connection, painting etc.as required. 60 nos	60.00	Nos.	
	3	7/F light plug point with piano type Accessories:- Supplying and fixing suitable size modular plate G.I./PVC box on surface or in recess with phenolic laminated sheet cover infront including providing and fixing 6Pin 15/16Amp modular socket outlet and 15/16Amp modular type switch connection, painiting etc.as required. 40 nos		Nos.	



DESCRIPTION OF THE PERSON OF T				
	Supplying and fixing 2pin ceiling rose on the existing junction box/wooden block including connection etc.as required. 18 nos	18.00	Nos.	
34	Supplying and fixing batten/angle holder including connection etc.as required. 30 each	30.00		
35	Installation Testing and commissioning of any interesting		Each	
	compact fluroescent fitting all type complete with all accessoires and tubes etc.directly/wall including connection witgh 1.5Sq.mm FRPVC insulated copper conductor single core cable and earthing etc.as required 78 nos	78.00	Nos.	
36	Supplying and fixing 6Amp to 32Amp rating 240Vls 10KA,"B" Series miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections testing and commissioning etc.as required			
	6/32Amp single pole"B" Series 9 nos	9.00	Nos.	
37	Supply of 9/10 watt LED blub 20 nos	20.00	Nos.	
38	Supply of LED batten (20/22W) 35 nos	35.00	Nos.	
39	Double LED tube light2x20Watt 68 nos	68.00	Nos.	
40	20/25W LED Opal approved make LED Post Top made in dia cast aluminum housing with decorative clear/opal/acrylic diffusers and IP65 protection IS10822 part 5/section 3 28 nos	28.00	Nos.	
	Total			0.00
	GST 18%			0.00
	Total			0.00
	Lobor Cess 1%			0.00
	Total			0.00
	Say			0.00

Chief Executive Officer
Jharkhand State Khadi
Village Industries Board, UdyogBhawan
Ratu Road, Ranchi.